

Abstract Details

Work Name	Work Code	Sub Division	Estimate Amount	Lumpsum Amount	Total Amount
Providing and Fixing Tree Guards and Dustbins at various locations under Ward no. 14 MCG	GUR01220210405154 321	Gurgaon	2497500.00	0.00	2497500.00

Item Code	Item Type	Item Description	Unit	Calculated on Rate	Quantity	Calculated Rate	Total Amount
NSITEM	NSITEM	-FRP Dustbin (Tilting Type) of capacity 60 LTR. Body is made of moulded fiberglass re-inforced plastic of 2mm thick having its lid with handle. It fitted with m.s square pipe 1.25" x 1.25" x 14 gauge & m.s flat 50 x 5mm, 30 x 5mm base structure with suitable PU Paints. Complete item with GST, Transportation, Installation with C.C & labor at site.	Each	NSADRate	100.00	8,560.00	856,000.00
NSITEM	NSITEM	-Tree Guards wiremesh 20"dia x4 ht .and overall 68 "hight made of M.s. wiremesh 1"x3"x3mm thick supports with angle 25mmx25mmx5mm and M.s. flat rings of 25mmx3mm thick of size 13"Lx9" Hight with writing of green Gurgaon by MCG including moulded tree marking on it and painted complete in all respect. (As per site with fixing)	Each	NSADRate	670.00	2,450.00	1,641,500.00
Total :					770.00	11,010.00	2,497,500.00