

WORK DETAIL

Work Name:- Development of two parks near Mandir in Sikenderpur, Ward 34, Gurugram

Work Code	GUR01220210130085650
Work Type	Horticulture
Work Sub Type	Horticulture
Work Created Date	1/30/2021 8:56:50 AM
MC Name	Gurgaon
Ward No.	34
Work Quantity	3000
Financial Year	2020-2021

Scheme Name	MC Fund
Scheme Component Name	MC Fund
Total Amount (Rs.)	2008197.81
Announcement Date	
Announcement Type	Others
Announcement No	
Status	Technically /
View Items (/Work/PrePareEstimatePreview?q=8IUDAKGX11LLIqEWdniNamyMEw08EkbB)	
View Abst	

REMARK

Remark	Remark By	Sent To	Remark Date	Status	Download File
Technically approved.	Devender Kumar	Mukesh Kumar Singhmar	3/23/2021 12:46:24 PM	Technically Approved	No File

Remark	Remark By	Sent To	Remark Date	Status	Download File
Submitted for Technical approval please	Mukesh Kumar Singhmar	Devender Kumar	3/20/2021 8:45:49 AM	Pending For Technical Approval	No File
Approved	Vijay Kumar	Mukesh Kumar Singhmar	3/19/2021 2:37:50 PM	Financially approved	No File
Submitted for approval please	Karambir Yadav	Vijay Kumar	3/19/2021 2:13:42 PM	Pending For Financial Approval	No File
Fund Allocated to the tune for Rs 20.08 from MC Fund the Head 410-23 Sports out of approved budget for the year 2020-2021 subject to approval of competent Authority.	Rajesh Gupta	Karambir Yadav	3/19/2021 2:10:36 PM	Pending For Financial Approval	No File
for financial approval please	Karambir Yadav	Rajesh Gupta	3/17/2021 5:02:46 PM	Pending For Financial Approval	No File
For necessary action	Vijay Kumar	Karambir Yadav	3/17/2021 3:54:10 PM	Pending For Financial Approval	No File
Submitted for Financial approval please	Mukesh Kumar Singhmar	Vijay Kumar	3/17/2021 11:57:35 AM	Pending For Financial Approval	No File
Approved as proposed	Hariom Attri	Mukesh Kumar Singhmar	3/17/2021 11:44:12 AM	Administratively Approved	No File
Forwarded in compliance of direction given by Ad CMC -IV to deal the files upto Rs.25 lakhs by the JCs.	Satyawan Singh	Hariom Attri	3/16/2021 5:07:20 PM	Pending for Administrative Approval	No File
Please send to concerned officer	Hariom Attri	Satyawan Singh	3/16/2021 5:00:48 PM	Pending for Administrative Approval	No File

Remark	Remark By	Sent To	Remark Date	Status	Download File
Keeping in view the attended observations recommended as proposed by EE - Horticulture II	Satyawan Singh	Hariom Attri	3/16/2021 4:22:27 PM	Pending for Administrative Approval	No File
Submitted for approval please	Devender Kumar	Satyawan Singh	3/16/2021 4:01:39 PM	Pending for Administrative Approval	No File
As per latest orders of W/CMC, the work files upto Rs. 25.00 lakhs are to be dealt through concerned SE.	T L Sharma	Devender Kumar	3/15/2021 2:10:21 PM	Pending for Administrative Approval	No File
The area councilor Sh R S Rathi along with villagers of Sikender Ghosi have been pressing hard since quit a long time for the beautification the MCG land lying vacant near village temple which is prone to encroachment as someone in the village having ill will to extend the mandir over there and want to encroach this land in the garb of religious sentiments so this estimate may please be approved in public interest. Resubmitted for approval please.	Devender Kumar	T L Sharma	3/3/2021 5:58:47 PM	Pending for Administrative Approval	No File
Submitted for Adminstrative Approval please	Mukesh Kumar Singhmar	Devender Kumar	3/3/2021 2:18:09 PM	Pending for Administrative Approval	Click Here (/Upload/Files/521857ee-7733-41d2-a54f-a6194233ec9d.pdf)
Please do as directed by Worthy CE	Devender Kumar	Mukesh Kumar Singhmar	3/2/2021 8:14:20 PM	Pending for Administrative Approval	No File

Remark	Remark By	Sent To	Remark Date	Status	Download File
Please put up complete estimate, showing site plan, layout plan, X-section, scope of work, photographs of proposed site with longitude and latitude. etc.	T L Sharma	Devender Kumar	2/19/2021 4:24:13 PM	Pending for Administrative Approval	No File
The site plant with schematic proposed plant and scope of work has been attached. Re Submitted for approval please	Devender Kumar	T L Sharma	2/15/2021 1:22:26 PM	Pending for Administrative Approval	No File
Sir, Document has been uploaded showing site plan, layout plan, X-section, scope of work. Submitted for approval please	Mukesh Kumar Singhmar	Devender Kumar	2/15/2021 11:45:38 AM	Pending for Administrative Approval	Click Here (/Upload/Files/295715de-8979-44a0-b5db-9bea103724df.pdf)
Complete the file as desired by worthy CE	Devender Kumar	Mukesh Kumar Singhmar	2/8/2021 6:57:18 PM	Pending for Administrative Approval	No File
The estimate is incomplete, please put up complete estimate, showing site plan, layout plan, X-section, scope of work etc.	T L Sharma	Devender Kumar	2/5/2021 7:47:44 PM	Pending for Administrative Approval	No File

Remark	Remark By	Sent To	Remark Date	Status	Download File
The area councilor Sh R S Rathi along with villagers of Sikender Ghosi have been pressing hard since quit a long time for the beautification the MCG land lying vacant near village temple which is prone to encroachment as someone in the village having ill will to extend the mandir over there and want to encroach this land in the garb of religious sentiments so this estimate may please be approved in public interest	Devender Kumar	T L Sharma	2/1/2021 6:29:07 PM	Pending for Administrative Approval	Click Here (/Upload/Files/9b814c38-7ac0-4f16-ac29-3158a5c1a803.pdf)
Sir, This estimate has been framed as demanded by Ward Committee. Submitted for approval please	Mukesh Kumar Singhmar	Devender Kumar	1/30/2021 10:32:36 AM	Pending for Administrative Approval	No File

WORK ITEMS

Item	Remarks	Numbers			Length	Breadth	Height	Unit	Qty	Item Type	View
10.k.2	Brick ballast for construction of front side park in Mandir	1.00	1.00	2.00	62.00	0.60	0.10	cum	7.44	+	No File
11.c.3	Brick work for construction of backside park in Mandir	1.00	1.00	1.00	82.00	0.23	0.90	cum	16.97	+	No File

Item	Remarks	Numbers			Length	Breadth	Height	Unit	Qty	Item Type	View
18.e.1	Square tube 25X25X2.6 mm for making grills of backside park in Mandir	1.00	25.00	2.00	0.30	0.01	1.00	Qtl	0.25	+	No File
ADITEM	Primer and paint	1.00	2.00	25.00	3.00	1.10	1.00	Square Meter	165.00	+	No File
10.f.2	Kerbs for making footpath of backside park in Mandir	1.00	2.00	2.00	80.00	0.15	0.30	cum	14.40	+	No File

Page 1 of 9.

1

2 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t1LsDXaFuxvfkoEf7r36vC5)

3 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t1IVw6CAwNdelMivHwO7AQh)

4 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t2FjiN8H3nfVFh%2FTAv2uakv)

5 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t2PTjK7SJEMsiMa2EFpIlua)

6 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t2NVzrmz26S2mtHkw9elsO6)

7 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t1sEDOXiYFNR3Q8CStr2aTe)

8 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t1mn%2BuqQmh0IgvUYF5SibQn)

9 (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t33C10y07UNKzPjgtr%2BNLj4)

» (/AssociateProject/AssignProject?q=r%2FI3S%2BVZ5t1LsDXaFuxvfkoEf7r36vC5)

CALCULATED ABSTRACT

Item Code	Description	Unit	Rate Type	Rate	Premium Rate	Total Rate	Quantity	Amount
-----------	-------------	------	-----------	------	--------------	------------	----------	--------

Item Code	Description	Unit	Rate Type	Rate	Premium Rate	Total Rate	Quantity	Amount
10.k.2	10.117.-Laying dry brick ballast (40 mm gauge)	cum	Through Rate	121.20	450.00	666.60	100.32	66873.31
NSITEM	-Supply and Planting of Ficus Black plant including digging of holes, cost of loading, unloading and planting in position including watering and labour cost with three months maintenance period complete in all respect.	Each	NSADRate			840.00	30.00	25200.00
10.f.2	10.77-Pre-cast cement concrete 1:2:4 with stone aggregate 20 mm nominal size in kerbs and the like items, finished smooth with 6 mm thick cement plaster 1:3 on exposed surface including form work, placing and fixing in position, complete at the ground level or in first storey.	cum	Through Rate	942.50	450.00	5183.75	14.40	74646.00

Item Code	Description	Unit	Rate Type	Rate	Premium Rate	Total Rate	Quantity	Amount
33.19	33.19.-Planting permanent hedges including digging of trenches, 60 cm wide and 45 cm deep, refilling the excavated earth, mixed with farm-yard manure, supplied at the rate of 4.65 cum per 100 metres and supplying and planting hedge at 30 cm apart.	mtrs	Labour Rate	2278.35	600.00	159.48	124.00	19776.07
6.b.i.a	6.6-Earth work in excavation in foundations, trenches, etc. in all kinds of soils, not exceeding 2 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction, including disposal of all surplus soil, as directed within a lead of 30 metres.	cum	Labour Rate	1108.10	425.00	58.17	103.28	6008.33
					Total Amount			2008197.81

2 (/AssociateProject/AssignProject?q=9NQUvnDzVPckY7R8WpcUQ6TvhLhREVs24xLWIWNO9oQ%3D)

3 (/AssociateProject/AssignProject?q=9NQUvnDzVPc976jt%2BinS86hJqEU0ZppzUelpNDfTips%3D)

4 (/AssociateProject/AssignProject?q=9NQUvnDzVPccm6WjiVYoeTLKaWiVqhRgjt%2FaYpXk0nU%3D)

» (/AssociateProject/AssignProject?q=9NQUvnDzVPckY7R8WpcUQ6TvhLhREVs24xLWIWNO9oQ%3D)

Copyright © 2019-2021. Directorate of Urban Local Bodies (<https://ulbharyana.gov.in>). All rights reserved.