Abstract Details

| Work Name | Work Code | Sub Division | Estimate Amount | Lumpsum Amount | Total Amount |
|--|--------------------------|--------------|--------------------|-------------------|-----------------|
| Construction of new RMC road from Groz Engineering near Kherki toll towards SPR road under Jurisdiction of MCG area. | GUR01220210219153 147 | Gurgaon | 9273606.56 | 463680.32 | 9737286.88 |

| Item Code | Item Type | Item Description | Unit | Calculated on Rate | Quantity | Calculated Rate | Total Amount |
|-----------|-----------|--|-------|-----------------------|----------|--------------------|--------------|
| 10.e.1 | HSRITEM | 10.63Design mix cement concrete of grade M-10 with minimum cement contents 220 kg/cum in foundation and plint. | cum | Through Rate | 487.50 | 2,985.12 | 1,455,248.43 |
| ADITEM | ADITEM | -(4.1A+5.2A) Stone sand bajri shingles spalls brick bats brick ballast stone metal malba within 10KM kead 31.25 | Cum | NSADRate | 5655.00 | 171.88 | 971,981.40 |
| NSITEM | NSITEM | -Providing and making sawcut longitudinal joints between two lanes including cost of providing prtective coating of bituminous paint for 75mm | Meter | NSADRate | 1835.50 | 51.00 | 93,610.50 |
| 9.13 | HSRITEM | 9.13Shuttering for faces of concrete foundations and foundations beams (vertical or battering) | sqm | Through Rate | 300.00 | 153.25 | 45,975.00 |
| 24.a.1 | HSRITEM | 24.1Preparation of sub grade, including trenching, rough dressing of spoil final dressing of earth,to given levels and camber, watering, rolling with road roller, and compacting the bed (Labour Rate A) | sqm | Labour Rate | 4875.00 | 3.90 | 19,017.37 |
| NSITEM | NSITEM | -Providing and Laying Separation membrane Sheet 125 micron thick imper able plastic sheet of approved quality of make IPCL, Shivalik or equivalent make, over the surface of DLC complete in all respects as per entire satisfaction of the Engineer-in-Charge. | | NSADRate | 4875.00 | 12.00 | 58,500.00 |
| 6.b.i.a | HSRITEM | 6.6-Earth work in excavation in foundations, trenches, etc. in all kinds of soils, not exceeding 2 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry, in 15 cm layers with compaction, including disposal of all surplus soil, as directed within a lead of 30 metres. | cum | Labour Rate | 975.00 | 58.17 | 56,720.86 |

| Total : | | | | Total : | 30001.00 | 10,061.82 | 9,273,606.56 |
|---------|--------|--|-----------------|----------|----------|-----------|--------------|
| NSITEM | NSITEM | -Providing and laying granular sub base (GSB) Grading-III SDS | Cum | NSADRate | 468.00 | 883.50 | 413,478.00 |
| NSITEM | NSITEM | -Dismentling of RMC 150mm to 200mm thick with hydroulic compresser mounted on JCB Complete. Rate=150/- | Square Meter | NSADRate | 4680.00 | 150.00 | 702,000.00 |
| NSITEM | NSITEM | -analysis of providing and laying in position machine batched, machine mixed and machine vibrated ready mixed cement concrete of grade M 40 with cement content not less then 420 kg/cum imparting minimum compressive strength of 40 mpa at 28 days | Cum | NSADRate | 975.00 | 5,592.00 | 5,452,200.00 |
| NSITEM | NSITEM | -Extra for making rough surface of the concrete pavement of providing non slippery by mechanical cutter for safe playing of vehicles as per entire satisfaction of the engineer-in-Charge | Square Meter | NSADRate | 4875.00 | 1.00 | 4,875.00 |