

WORK DETAIL

Work Name :- Estimate for Providing and fixing Canopy at sector-23A Parks,Ward No.-2,Zone-II,Gurugram.

Work Code	GUR01220210819104826
Work Type	Horticulture
Work Sub Type	Horticulture
Work Created Date	8/19/2021 10:48:26 AM
MC Name	Gurgaon
Ward No.	2
Work Quantity	1000
Financial Year	2021-2022

Scheme Name	MC Fund
Scheme Component Name	MC Fund
Total Amount (Rs.)	2184000.00
Announcement Date	
Announcement Type	Others
Announcement No	
Status	Technically Approved
View Items (/Work/PrePareEstimatePreview?q=q0mD5PHEzuFdqPR3XUuMjiGa32o8kEWA)	View Abstracts (/Work/PrePareEstimatePreview?q=q0mD5PHEzuFdqPR3XUuMjiGa32o8kEWA)

REMARK

Remark	Remark By	Sent To	Remark Date	Status	Download File
Technically approved	Devender Kumar	Gulshan Yadav	9/11/2021 12:52:05 PM	Technically Approved	No File
Submitted for technical approval please.	Gulshan Yadav	Devender Kumar	9/7/2021 3:15:47 PM	Pending For Technical Approval	No File
APPROVED	Vijay Kumar	Gulshan Yadav	9/7/2021 3:04:51 PM	Financially approved	No File
Submitted for approval please	Karambir Yadav	Vijay Kumar	9/7/2021 11:30:52 AM	Pending For Financial Approval	No File

Remark	Remark By	Sent To	Remark Date	Status	Download File
Fund Allocated to the tune for Rs 21.84 lacs from MC Fund the Head 410-23 Sports and health parks and grounds out of approved budget for the year 2021-2022 subject to approval of competent Authority.	Bhupender Singh	Karambir Yadav	9/6/2021 12:17:23 PM	Pending For Financial Approval	No File
For necessary action please.	Karambir Yadav	Bhupender Singh	9/6/2021 11:52:08 AM	Pending For Financial Approval	No File
For necessary action please.	Vijay Kumar	Karambir Yadav	9/6/2021 10:51:15 AM	Pending For Financial Approval	No File
As proposed	Mukesh Kumar	Vijay Kumar	9/5/2021 7:55:06 AM	Pending For Financial Approval	No File
File is submitted for information before financial approval to be given by accounts branch.	Vijay Kumar	Mukesh Kumar	8/27/2021 3:48:25 PM	Pending For Financial Approval	No File
Submitted to W/CMC for kind perusal please.	Karambir Yadav	Vijay Kumar	8/26/2021 3:14:27 PM	Pending For Financial Approval	No File
As discuss, file is Checked for Rs. 21.84 lacs and file is submitted to W/CMC for kind perusal.	Bhupender Singh	Karambir Yadav	8/26/2021 2:35:52 PM	Pending For Financial Approval	No File
For necessary action please.	Karambir Yadav	Bhupender Singh	8/25/2021 3:03:51 PM	Pending For Financial Approval	No File
For necessary action please.	Vijay Kumar	Karambir Yadav	8/25/2021 2:27:14 PM	Pending For Financial Approval	No File
submitted for financial approval please	Gulshan Yadav	Vijay Kumar	8/24/2021 8:27:55 PM	Pending For Financial Approval	No File
Approved	Subhash Yadav	Gulshan Yadav	8/24/2021 5:06:00 PM	Administratively Approved	No File
Demand letter of the councilor is attached. Resubmitted for approval please.	Devender Kumar	Subhash Yadav	8/23/2021 5:45:52 PM	Pending for Administrative Approval	Click Here (/Upload/Files/bc0cc4a5-179e-4794-8e69-134f002c79b7.pdf)
Whether it is required or on demand of Councilor	Subhash Yadav	Devender Kumar	8/23/2021 5:14:19 PM	Pending for Administrative Approval	No File
Submitted for approval please	Devender Kumar	Subhash Yadav	8/23/2021 2:54:41 PM	Pending for Administrative Approval	No File

Remark	Remark By	Sent To	Remark Date	Status	Download File
Sir, Now the rates have been revised by constituting the committee of JE,AE and EE. Now the rates 18x18 size canopy have been fixed 3.12 lakhs only. Resubmitted for approval please.	Gulshan Yadav	Devender Kumar	8/23/2021 1:10:20 PM	Pending for Administrative Approval	No File
Whether the specification are same as it happened to be in case of the empaneled agency HIMCON	Devender Kumar	Gulshan Yadav	8/21/2021 1:52:35 PM	Pending for Administrative Approval	No File
Submitted for approval please.	Gulshan Yadav	Devender Kumar	8/19/2021 2:25:35 PM	Pending for Administrative Approval	No File

WORK ITEMS

Item	Remarks	Numbers	Length	Breadth	Height	Unit	Qty	Item Type	View	
NSITEM	For Sec 23 A Parks	7.00	-	-	-	-	Each	7.00	+	View (/Upload/Item/GUR012/741093bb-059c-4ff

CALCULATED ABSTRACT

Item Code	Description	Unit	Rate Type	Rate	Premium Rate	Total Rate	Quantity	Amount
-----------	-------------	------	-----------	------	--------------	------------	----------	--------

Item Code	Description	Unit	Rate Type	Rate	Premium Rate	Total Rate	Quantity	Amount
NSITEM	<p>-(i) 6 No. Ornamental Design FRP Molded Pillar FRP base pedestal with vertical fitted design having base width of size 260mm x 260mm and height 900mm having 4 no. of size 20mm drilled in the base with hold fasts and having B class vertical m.s pipe of size 88 mm and height 2890mm, the central m.s pipe holds FRP Molded taj 6 no of size 260 x 260 x 210mm high suitably mounted at appropriate height complete as per design. Complete pillar suitably grinded and subsequently spray painted with two coats of P.U Paints in required shade. (ii) 12 No. spndred and 6 no. Friezes Floral and Ornate decorative design combination of spandrel and frieze, matched to be suspended between two m.s pillars as per the design. The spandrel (L-Bracket) having length 420mm and height 400mm the frieze (Top Panel) height 250mm and length as per the size of the gazebo. The frieze mounted on m.s tabular pipe frame of size 50mm x 25mm, frieze properly welded to the column pillars at either ends. Complete set of spandrel & frieze uniformly grinded spray primered, spray painted with P.U Paints. (iii) 3 No. cast iron/frp base panel railing with frame Floral and Ornate decorative design cast iron/frp side railing panel as per design having height of 730mm and length as per size of Gazebo. Each panel top and bottom mounted with mild steel tubular pipe frame of size 50 x 25 mm. The bottom mild steel pipe having 2 nos. of hold fasts in m.s pipe of size 40 x 40mm and length 250mm welded at the base to hold the panel in the ground. Every panel length is as per the gap between the two pillars. The complete railing panel grinded for neat surface finishes spray primered and subsequently spray painted with P.U Paint in required shade. (iv) One set of top frame with Double Finishing FRP Molded Plastic Sheet roof Top frame in m.s tubular pipe of size 40 x 40mm properly welded and grinded. The top frame mounted with FRP molded Sheet of 4 mm thick with top & bottom good finishing (Double finishing sheet) to make it rust proof bent to profile of size 245mm width in -Z- section on either ends fixed horizontally along the length between column pillars. Also it contain FRP Moulded Ball of 14"Dia x 2mm thick at the central top for its beautification. Each sheet enamel painted in red color. Each such sheet properly riveted to horizontal sheets. The complete item is fitting at site with installation. (Including all types of Taxes and other charges.)</p>	Each	NSADRate			312000.00	7.00	2184000.00

Item Code	Description	Unit	Rate Type	Rate	Premium Rate	Total Rate	Quantiy	Amount
					Total Amount			2184000.00